


NARROW PICKET WROUGHT IRON NOTES:

1. 1/2" PICKETS @ 2" O.C. NO OPENING TO BE GREATER THAN 1 3/4"
2. 1" RAILS TOP & BOTTOM, 1" POST EACH SIDE
3. RETAINS 50% OPENNESS
4. BOTTOM RAIL TO BE ANCHORED TO TOP OF RETAINING WALL AND SET FLUSH W/OUTSIDE EDGE OF WALL.

GENERAL NOTES

5. RELEASE MECHANISM OF THE SELF LATCHING DEVICE SHALL BE LOCATED NOT LESS THAN 54" ABOVE BOTTOM OF GATE AND 3" BELOW THE TOP OF THE GATE ON POOL SIDE.
6. IF RELEASE MECHANISM IS LOCATED LESS THAN 54" ABOVE BOTTOM OF GATE. THEN PROVIDE AN AREA WHERE NO OPENING IS GREATER THAN 1/2" WITHIN 18" OF RELEASE MECHANISM.



REVISED 8/27/25



TOWN OF FOUNTAIN HILLS
STANDARD DETAIL

**TERRACED LOT
POOL ENCLOSURE DETAIL**

DETAIL NO.
FHTLPE

DETAILS N.T.S.